No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
19	Burnt brick in chunnam mortar, plastering with mortar building wall over roof, at ends ..	R.ft.	0 3 0	64	
20	Cement painting to basement alround	Sqr.	3 0 0	2·41	
21	Teakwood eave-boards plain 9″×$\frac{3}{4}$″ and fixing, etc., complete	R.ft.	0 7 0	146	
22	Teakwood turned finials and fixing, etc., complete	No.	3 0 0	2	
23	Teakwood pendents and fixing etc., complete ..	No.	1 0 0	4	
24	Chocolate painting including scaffolding charges.	Sqr.	3 0 0	7·64	
25	Clearing site and levelling the ground, etc., complete	Lumpsum Rupees.			

R. TIPPAIYA,
Executive Engineer.

MYSORE DIVISION.

Notification dated 7th February 1938.

It is hereby notified that the 1st Class Travellers' Bungalow at Hunsur will be closed for the public on Tuesday the 22nd February 1938 on account of Dewan's tour.

B. KRISHNA RAO,
Executive Engineer.

OFFICE OF THE ASSISTANT ENGINEER, HEADQUARTER RANGE, MYSORE.

Abstract Notification dated 26th January 1938.

The attention of the public is invited to the Notification published in Part VI, pages 152-158 of the *Mysore Gazette*, dated the 3rd February 1938, calling for sealed tenders for 'Construction of Pathological Institute in the premises of Krishnarajendra Hospital, Mysore.'

The last date for receiving tender is 21st February 1938. Earnest money to be deposited with the tender is Rs. 1,450.

Abstract Notification dated the 5th February 1938.

The attention of the public is invited to the Notification published in pages 193-198, Part VI of the *Mysore Gazette*, dated 10th February 1938, calling for sealed tenders for the construction of Anatomy Block on the western side of the Medical College, Mysore.

The earnest money to be deposited along with the tender is Rs. 1,700.

The last date of receiving tenders in sealed covers is 18th February 1938 before 3 P.M.

Abstract Notification dated the 5th February 1938.

The attention of the public is invited to the Notification published in pages 198-202, Part VI of the *Mysore Gazette*, dated the 10th February 1938, calling for sealed tenders for the construction of Krishnarajendra Police Station at Mysore.

The earnest money to be deposited along with the tender is Rs. 380.

The last date for receiving tenders is 26th February 1938, before 3 P.M.

Notification dated 10th February 1938.

1. Sealed tenders will be received at the office of the Assistant Engineer, Headquarter Range, Mysore, upto 3 P.M. on 25th February 1938, for constructing European special ward in Krishnarajendra Hospital, Mysore.

2. Tenders in the prescribed form obtainable from the office of the Assistant Engineer, Headquarter Range, Mysore, on payment of rupee one for each form, should be addressed to the Assistant Engineer, Headquarter Range, and should be superscribed as "Tender for constructing European special ward in Krishnarajendra Hospital, at Mysore." The name of the tenderer should also be superscribed on the sealed cover.

3. Each tender must be accompanied by a deposit of Rs. 325 only in cash as earnest money. The earnest money of the successful tenderer will be retained as cash security deposit for the due fulfilment of the contract. (Cash amount will not carry any interest.) In case of the acceptance of the tender, an addition of the five per cent of the estimated amount as security deposit should be paid at the time of executing the agreement in the Public Works Department Form.

4. The tenders will be opened in the presence of such tenderers who wish to be present on 25th February 1938 at 4 P.M. The final acceptance of the tender will rest with the Assistant Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reasons whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Assistant Engineer's Office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute the agreement in the departmental schedule contract form, for the due fulfilment of the contract.

6. Failure to comply with the condition 5 above or to agree to carry out the work in accordance with the specifications and agreements in force will entail forfeiture of the earnest money.

7. Copies of contract documents, estimates and drawings may be seen at any time at the office of the Assistant Engineer, Headquarter Range, Mysore, on all working days, between 11 A.M. and 5 P.M.

8. Specific rates should be given for each item in the schedule and the rates should be in rupees, annas and in multiples of three pies and expressed in words and figures.

9. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer will not be taken notice of. The rates tendered should include all such lumpsum items.

10. No alterations which are made by the tenderers in the contract documents in the nomenclature of the sanctioned sub-heads will be recognised and if corrections are made, the tenders will be liable to rejection.

11. There should be no corrections or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

12. No reference should be made to the Public Works Department for the current schedule of rates.

13. On the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof or in the event of absence of any partner, it must be signed on his behalf by a person holding power of attorney authorising him to do so.

14. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates to be proposed by the Assistant Engineer, Headquarter Range, Mysore, and approved by the Superintending Engineer shall be final and legally binding on the tenderer.

15. The quantities as estimated are only approximate and are liable to alterations, omissions, deductions or additions, at the discretion of the Assistant Engineer or his representative. The tendered rates will hold good for any quantity whether higher or lower than those estimated for.

16. The work should be completed as per departmental specifications for different items and handed over to the Public Works Department by the end of May 1938, failing which the Assistant Engineer may, at his discretion, levy a penalty up to Rs. 50 per day, which will be recovered from the contractor's outstandings for the period exceeded by him till the work is completed and handed over.

17. In all matters of dispute of any kind, not specially provided for in the agreement or of rates, penalties, measurements, quality of work, etc., the decision of the Chief Engineer shall be final and legally binding.

18. The earnest money of rejected tenders will be returned on surrender of the receipts originally granted, along with an application to the Assistant Engineer, Headquarter Range, Mysore.

19. No claims for damages for delays caused by officers of the department in the execution of the work will be considered, whatever may be the reason for such delays. Contractors should bear this in mind when tendering for work. Extension of time due to delays caused by the departmental officers will, however, be considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools, plant and machinery that will be supplied by the Assistant Engineer in the interest of the work shall be accepted by the tenderer at the rates fixed by the Assistant Engineer and the tenderer will pay the hire, etc., on machinery at the prescribed per cent per annum of the booked value of the tools and plant supplied from the date of taking over of tools and plant from the Stores to the date of return to the Stores, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The contractors should arrange for the payment of royalty and tolls.

NOTE.—(*a*) The contractors should at their own cost—

(1) Provide rods, stakes, ropes and labours required in setting out the works.

(2) Provide all necessary scaffolding, centering, labour and appliance for hoisting.

(3) Provide mortar mill and shed to keep materials under cover and also for workmen.

(4) Arrange for protecting work during inclement weather.

(5) Supply requisite temporary lights, water cisterns, water-shoots, coverings to masonry, tile pieces to steps, sieves, parahs or measures, shoring and other requisite protection during the progress of the work.

(6) Supply all water required for work and workmen and shall provide latrines, drainages, etc.

(7) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.

(8) Provide arrangements for pumping and bailing from excavations and foundations, wherever and whenever necessary, with their own pumping apparatus including necessary leading drains, slump pits, etc.

(9) Wash floors at completion and leave the whole of the work and premises in a clean and orderly condition, etc.

(10) Afford facilities to any other parties employed upon the work, so that their work may proceed during the progress of the contract and give such persons the use of ordinary scaffolding and ladders.

NOTE.—(*b*) It is the business of the contractors to make their own arrangements for the quarries and supplies of materials.

23. The rates for wood-work for all works quoted should be based on the rates of the departmental supply as noted below. Only Mysore teak selected from the Mysore Government Depots must be used.

24. Work to the extent of Rs. 2,500 will have to be carried out each month.

Prevailing Government rates at Mysore Forest Depot for Mysore Teak is as follows :—

	Rs.	a.	p.	
(1) Selected 1st class logs ..	2	8	0	per c.ft.
(2) Cut scantling of sizes 3″×4″ ..	3	4	0	,,
(2) (*a*) Do 3″×5″ to 4″×7″	3	12	0	,,
(3) Planks 1″ to 1¾″ to required sizes ..	4	8	0	,,

Abstract of estimated quantities for constructing European Special Ward in Krishnarajendra Hospital, Mysore.

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
1	Earthwork excavation for foundation in hard gravelly soil and filling in basement with watering and tamping etc., complete ..	C.yd.		53	
2	Filling in foundation with broken granite stone jelly concrete in lime mortar, in layers not more than 6″ thick including watering and tamping	C ft		606	
3	Filling with burnt brick in lime mortar for foundation and basement ..	C.ft.		1,503	
4	Burnt brick in lime mortar for superstructure ..	C.ft.		1,674	
5	Burnt stone slabs 6″ thick, one line dressed and fixed on mortar bed	S.ft.		181	
6	Cement concrete slabs (1 : 2 : 4) including fixing on mortar bed	C.ft.		148	
7	Constructing pillars ¾′ square, with wire cut brick in composite mortar, with cement concrete bond slabs at every 3′ height including base and capitals of cement concrete including chunnam plastering, white or colour washing, as per design complete	Each		21	

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
8	Providing and fixing T. W. doors of frames $3\frac{1}{2}'' \times 4\frac{1}{2}''$ without bottom sills having half glazed and half pannel shutters $1\frac{1}{2}''$ thick with superior rim locks, with handles, hinges, hooks, etc., as per specification, complete ..	S.ft.		255	
9	Providing and fixing T. W. windows with frames $3'' \times 4''$ with half glazed and half venetianed shutters with ground glass, including $\frac{3}{4}''$ thick round bars (iron), brass hinges, bolts, nuts, etc., complete	S.ft.		126	
10	Providing and fixing rectangular T. W. ventilators with 1" thick round iron bars with glazed shutters including brass and iron fixtures, complete	S.ft.		54	
11	X-met partition with burnt brick in cement mortar with X-met at every third course, including chunam plastering, complete ..	S.ft.		823	
12	Providing and fixing R. S. Girders of B. S. S. (tested) including hoisting and with one coat of anti-corrosive paint, etc., complete ..	Cwt.		44	
13	Boxing up girders $12'' \times 5''$ and $3'' \times 6''$ with terrace bricks in cement mortar and reinforcements with galvanized steel-textied from above and chunam plastering, white or colour washing, etc., complete	R.ft.		85	
14	Roofing with R. C. C. of broken granite jelly (1 : 2 : 4) and brick, the reinforcements being $\frac{3}{8}''$ bars for spans less than 10' placed at $4\frac{1}{2}''$ apart, centre to centre, and with negative moment and distribution bars and 2" cross and longitudinal joints and with 3" layer of sukri concrete and then 3" of cement stone jelly concrete and with 3 courses of flat tiles and $\frac{1}{2}''$ top and ceiling plastering, including coving as per design, white-washing, etc., complete	Sqr.		19·18	
15	Constructing band cornice as per design 6" to 8" high, complete	R.ft.		138	
16	Plastering with chunam mortar smooth including rounding off corners if necessary and the plaster on outer face being ground with yellow Ochre to a certain tint, complete	Sqr.		37·46	
17	White and colour washing, 2 coats	Sqr.		37·46	
18	Skirting to walls in cement including colouring, 9" high, complete	R.ft.		350	
19	Dadoing walls with silicate paints with 2 coats	Sqr.		10·84	
20	Border paint superior as per approved tint 3" wide	R.ft.		362	
21	Constructing plain parapet wall for verandah with burnt brick in mortar 9" thick and $1\frac{1}{2}''$ high, including nase and top as per design and plastering, white and colour washing, etc., complete	R.ft.		147	
22	Flooring with $1\frac{1}{2}''$ cement concrete (1 : 2 : 4) jelly to be of granite metal over 4" lime concrete with topping of red cement $\frac{1}{4}''$ thick finished with ironite $2\frac{1}{2}$ lbs. per square and cut to tile pattern where required with all corners rounded, etc., complete	Sqr.		15·38	
23	Painting two coats with superior Dulux Grey Paint, two coats	Sqr.		8·10	

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
24	Constructing parapet wall ¾′ thick as per design, 1½′ to 2′ high with burnt brick in lime mortar and plastering, white or colour washing, etc., complete for the main building	R.ft.		131	
25	Providing and fixing 4″ dia. C. I. down take rain water pipes with gratings, heads, elbows, bends, etc., with required colour painting with necessary fixtures, etc., complete ..	R.ft.		190	
	Alternative Items.				
1	Granite cut stone pillars 9″ square with base and capitals as per design neatly dressed including fixing	Each		21	
2	Roofing with reinforced joists (as per specification) and brick nogged terrace with 4″ kappi in quick lime and 3″ cement stone jelly concrete on top and ½″ thick cement plastering including ¼″ thick coloured water proof cement at top, surface finished smooth and cut to tile pattern, etc., including ceiling, plastering, coving as per design, white-washing, etc., complete	Sqr.		19.18	

M. A. RAMANUJAM,
Assistant Engineer.

HASSAN DIVISION.

Abstract Notification dated the 6th February 1938.

The attention of the public is invited to the Notification published in *Myosre Gazette* dated 10th February 1938, *vide* pages 202-204, Part VI, calling for tenders for "Constructing first floor to the Administrative Block of Sri Chamarajendra Hospital at Hassan". The last date for receipt of tenders is 26th February 1938.

D. A. HUKERI,
Executive Engineer.

MEDICAL DEPARTMENT

KRISHNARAJENDRA HOSPITAL, MYSORE.

TENDER NOTICE.

Dated 10th February 1938.

Notice is hereby given that sealed tenders on half-sheet of foolscap size paper, in triplicate, will be received at the Office of the Medical Officer, Krishnarajendra Hospital, Mysore, by the Medical Officer, at 11 A.M., on Saturday the 5th March 1938 for the supply of Bedding and Clothing (as per list annexed) required for the Krishnarajendra Hospital, Mysore, for the year 1938.

2. No tender will be received after the hour and date abovementioned.

3. Tenders to be superscribed "Tender for the supply of Bedding and Clothing to the Krishnarajendra Hospital, Mysore."

4. No tender will be received unless accompanied by a deposit of Rs. 150 in treasury receipts.

5. Tenders will be opened by the Medical Officer in charge at his office (Krishnarajendra Hospital, Mysore) on the day and at the hour abovementioned in the presence of such of the tenderers as may choose to attend.

6. The rate of each item must be specified in figures as well as in words and they must be for the particular kind or brand of the articles as specified in the list appended hereto. The value of each tender must be worked out according to the rates tendered and the total value must also be entered in ink. Tenders not conforming to this rule will be rejected.

7. The quantities stated in the list are not guaranteed.